

City of Prescott
Public Works Department
433 North Virginia Street
Prescott AZ 86301



Visit www.prescott-az.gov
for more information.



Sundog WWTP Septage Station Improvements

March 2025

UTILITY PROJECT

The City's Sundog WWTP receives septage from commercial haulers and recreational vehicles at its septage station, which was constructed in the 1980s and upgraded several times since. The vehicle offloading area lacks containment for wastewater spills and equipment wash-down. During a recent Stormwater Pollution Prevention inspection by ADEQ, the lack of spill containment resulted in a Notice of Opportunity to Correct Deficiencies (NOC). This project is necessary to provide stormwater pollution prevention at the site and to comply with the terms of the NOC.

The project generally consists of removing and replacing the septage station off-load driveway and the installation of a catch basin in the off-load driveway and a containment curb along the perimeter of the septage station vault.

The City has negotiated a contract with J. Banicki Construction (Banicki), a contractor from the City's Job Order Contracting list, to expedite the improvements. The contract was approved at the January 28, 2025, Council meeting.

The Notice to Proceed will be issued for March 3, 2025, and construction will start the same day. The City anticipates completing construction by April 2, 2025.

City Contact Information

Project Manager: Scott Balck

Phone: (928) 777-1130