



ADDENDUM NUMBER ONE

FOR THE

PLEASANT STREET PAVEMENT & DRAINAGE REPAIRS

DATE OF ADDENDUM: July 17, 2025

TO ALL BIDDERS BIDDING ON THE ABOVE PROJECT:

The following addendum shall be made part of the Project Specifications and Contract Documents. All other provisions of the Contract Documents remain unchanged. The Bidder shall acknowledge receipt of this Addendum on page 10 of the Bid Proposal form, in addition to signing below and returning this form with the bid package. The contents of this Addendum shall be given full consideration in the preparation of the Bid.

Changes to the Bid Schedule

On Pages 7 and 8 Bid Schedule:

REMOVE the Bid Schedule in its entirety and REPLACE it with the REVISED BID SCHEDULE dated July 8, 2025 (attached).

- END -

City of Prescott Public Works Department

Gwen

Rowitsch

Digitally signed by Gwen
Rowitsch
Date: 2025.07.17 10:55:47
-07'00'

Gwen Rowitsch, Public Works Director

Date

Acknowledgement: (must be signed and turned in with the bid documents)

Company Name

Signature of Company Official

Date

Bidding Schedule

Pleasant Street Pavement & Drainage Repairs

CIP: 2406-004

Revised July 8, 2025

Line No.	Item	Description	Qty	Unit	Unity Cost	Amount
General Construction Items						
1	105.8	CONSTRUCTION STAKING	1	LS		
2	107.15	PUBLIC RELATIONS ALLOWANCE	1	ALL	\$8,000.00	\$ 8,000.00
3	107.16	STORMWATER POLLUTION PREVENTION PLAN (SWPPP)	1	LS		
4	109.10	MOBILIZATION/DEMOBILIZATION	1	LS		
5	109.11	CONTRACT ALLOWANCE	1	ALL	\$100,000.00	\$ 100,000.00
6	401	TRAFFIC CONTROL PLAN	1	LS		
7	401.2	TRAFFIC CONTROL DEVICES	1	LS		
8	401.3	FLAGGERS	120	HR		
<i>General Construction Items</i>					\$	
Roadway and Drainage Improvements						
9	205.1.1 SP	EARTHWORK (OVER-EXCAVATION)	1053	CY		
10	205.2 SP	UNSUITABLE MATERIAL (PROVISIONAL)	100	CY		
11	301	SUBGRADE PREPARATION	1,580	SY		
12	306	GEOGRID TENSAR NX-750	1,485	SY		
13	310	6" ABC FOR ROADWAY	248	CY		
14	321 SP	ASPHALT CONCRETE PAVEMENT, 4" THICK, (3/4" MARSHALL MIX)	1,485	SY		
15	340	CONCRETE VERTICAL CURB AND GUTTER PER QCSD 220Q-1 TYPE 'A'	452	LF		
16	340.3 SP	REMOVE AND REPLACE SIDEWALK, STEPS WEST OF NEW CATCH BASIN	1	LS		
17	340.3.3.3	DRIVEWAY ENTRANCE PER QCSD 250Q-1	246	SF		
18	345.4	ADJUST WATER VALVE FRAME AND COVER	2	EA		
19	345.5	ADJUST SEWER MANHOLE FRAME AND COVER	3	EA		
20	350.3	REMOVAL OF PAVEMENT	1485	SY		
21	350.5	REMOVAL OF MISCELLANEOUS CONCRETE (EX CURB)	452	LF		
22	350.4	STORM PIPE REMOVAL	34	LF		
23	350.5	CATCH BASIN REMOVAL	2	EA		
24	107.9	MAILBOX (REMOVE AND REINSTALL)	2	EA		

Bidding Schedule

Pleasant Street Pavement & Drainage Repairs

CIP: 2406-004

Revised July 8, 2025

Line No.	Item	Description	Qty	Unit	Unity Cost	Amount
25	350.5	REMOVAL OF MISCELLANEOUS CONCRETE (EX DRIVEWAY)	225	SF		
26	402	PAVEMENT MARKINGS (DOUBLE YELLOW STRIPE)	1,056	LF		
27	505	CATCH BASIN PER MAG SD 533 TYPE 'D' - L=3'	1	EA		
<i>Roadway and Drainage Improvements</i>					\$	
Total Bid Amount			\$			

TOTAL BID AMOUNT:

Dollars and Cents

(In Written Words)

Company Name

Company Address

Signature of Company Official

Date Signed

Title

Email