City of Prescott
Public Works Department
433 North Virginia Street
Prescott, AZ 86301

Visit www.prescott-az.gov for more information.

Ken Lindley Green Stormwater Infrastructure

November 2026

UTILITY PROJECT

As part of the City of Prescott Green Stormwater Infrastructure Program, Public Works is designing rainwater harvesting, erosion control, and stormwater filtering vegetated areas along right-of-way between East Willis Street and the Ken Lindley Skate Park.

The project consists of curb cuts, sediment traps, and vegetated stormwater basins. These features will be designed to trap sediment, filter stormwater, and beautify the park and surrounding area while providing a sound and visual buffer for park users. Stormwater features will reduce *E. Coli* loads into the Virginia St Wash, which carries a USEPA impairment for high *E. Coli* and low dissolved oxygen.

30% conceptual designs have been initiated alongside utility locating and surveying, which are all anticipated to be completed in November 2026.

City Contact Information

Project Manager: Jeremy Cordova

Phone: (928) 777-1130