City of Prescott
Public Works Department
433 North Virginia Street
Prescott AZ 86301

Visit www.prescott-az.gov
for more information.

Wildwood Gravity Sewer Improvements

November 2026

UTILITY PROJECT

The project will replace an old, failing sanitary sewer lift station and sewer force main, located behind 15 Highland Terrace, within the Wildwood Estates Subdivision, with a gravity sewer main. Due to its location and the topography, the lift station is very difficult to access and maintain. The City will replace the lift station and force main with a new sanitary sewer manhole, connect the existing house sewer services to the new manhole, and reroute the wastewater to the new gravity sewer main extending from Wildwood Drive.

Civiltec was awarded a design services contract in September 2024. The City has coordinated with property owners and secured temporary construction and permanent sewer easements required for the new gravity sanitary sewer main.

A 100% design review was completed in April 2026. The City plans to complete design by the end of 2026, bid, award, and start construction in early 2027, and complete construction by the end of 2027.

City Contact Information

Project Manager: Scott Balck

Phone: (928) 777-1130